



AFRL-SA-WP-TR-2024-0012

Missile Community Cancer Study, Round 3 Radon Results for Malmstrom, F.E. Warren, and Minot Air Force Base



**Lt Col Scott M. Boyd
Occupational & Environmental Health Department**

**Report Date
25 September 2024**



DISTRIBUTION STATEMENT A. Clearance number is AFRL-2024-4927. Approved for public release: distribution is unlimited. 25 September 2024. Other requests shall be referred to DCPH-D/OEC, 2510 Fifth St., Bldg. 840, Wright-Patterson AFB, OH 45433-7913.

**Date of Determination: 25 September 2024
Air Force Research Laboratory 711th Human Performance Wing
U.S. Air Force School of Aerospace Medicine
Occupational & Env. Health 2510 Fifth St.,
Bldg. 840
Wright-Patterson AFB, OH 45433-7913**

NOTICE AND SIGNATURE PAGE

Using Government drawings, specifications, or other data included in this document for any purpose other than Government procurement does not in any way obligate the U.S. Government. The fact that the Government formulated or supplied the drawings, specifications, or other data does not license the holder or any other person or corporation; or convey any rights or permission to manufacture, use, or sell any patented invention that may relate to them.

Qualified requestors may obtain copies of this report from the Defense Technical Information Center (DTIC) (<http://www.dtic.mil>).

AFRL-SA-WP-TR-2024-0012 has been reviewed and is approved for publication in accordance with assigned distribution statement.

SCOTT M. BOYD, Lt Col, USAF, BSC
Chief Consulting Executive
Occupational and Environmental Health
Department

JOANNA L. RENTES, Col, USAF, BSC
Chair, Occupational & Environmental Health
Department

This report is published in the interest of scientific and technical information exchange and its publication does not constitute the Government's approval or disapproval of its ideas or findings.

REPORT DOCUMENTATION PAGE

PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ORGANIZATION.

1. REPORT DATE 25 Sep 2024		2. REPORT TYPE CONSULTATIVE LETTER		3. DATES COVERED	
				START DATE 11 Dec 2023	END DATE 15 Apr 2024
4. TITLE AND SUBTITLE Missile Community Cancer Study, Round 3 Radon Results for Malmstrom, F.E. Warren, and Minot Air Force Base (AFB)					
5a. CONTRACT NUMBER		5b. GRANT NUMBER		5c. PROGRAM ELEMENT NUMBER	
5d. PROJECT NUMBER		5e. TASK NUMBER		5f. WORK UNIT NUMBER	
6. AUTHOR(S) Capt Leigh M. Durden, Occupational and Environmental Health Department					
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Air Force Research Laboratory, 711th Human Performance Wing U.S. Air Force School of Aerospace Medicine, Occupational & Env. Health Dept 2510 Fifth St., Bldg. 840 Wright-Patterson AFB, OH 45433-7913				8. PERFORMING ORGANIZATION REPORT NUMBER AFRL-SA-WP-TR-2024-0012	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Air Force Research Laboratory, 711th Human Performance Wing U.S. Air Force School of Aerospace Medicine, Occupational & Env. Health Dept 2510 Fifth St., Bldg. 840 Wright-Patterson AFB, OH 45433-7913			10. SPONSOR/MONITOR'S ACRONYM(S)	11. SPONSOR/MONITOR'S REPORT NUMBER(S) AFRL-SA-WP-TR-2024-0012	
12. DISTRIBUTION/AVAILABILITY STATEMENT DISTRIBUTION A. Clearance number is AFRL-2024-4927. Approved for public release: distribution is unlimited. 25 September 2024. Other requests shall be referred to DCPH-D/OEC, 2510 Fifth St., Bldg. 840, Wright-Patterson AFB, OH 45433-7913.					
13. SUPPLEMENTARY NOTES					
14. ABSTRACT At the request of the Air Force Global Strike Commander (AFGSC/CC), the United States Air Force School of Aerospace Medicine (USAFSAM) Defense Centers for Public Health-Dayton Occupational and Environmental Health Department (DCPH-D/OE) performed an environmental health survey for all forty-five Missile Alert Facilities (MAFs) at Malmstrom AFB, Montana; F.E. Warren AFB, Wyoming; and Minot AFB, North Dakota. The purpose of this environmental health survey was to assess elevated cancer concerns within the Air Force missile community by characterizing and documenting potential exposures to environmental hazards in the MAFs. Round 3 sampling occurred from 11 December 2023 to 15 April 2024 and built upon the Round 1 environmental health survey which occurred from 8 June 2023 to 3 October 2023 and the Round 2 environmental health survey which occurred from 8 September 2023 to 11 January 2024. Round 3 was executed as part of a three-round surveillance effort to determine seasonal variations associated with potential environmental hazards at MAF locations. Round 3 repeated area air sampling, direct reading instrument (DRI) air monitoring, drinking water sampling, and soil sampling which were conducted in Rounds 1 & 2. The purpose of this memo is to augment the Round 3 interim reports by conveying Round 3 radon results analyzed by DCPH-D/OE.					
15. SUBJECT TERMS Missile Community Cancer Study, Round 3 Radon Results for Malmstrom, F.E. Warren, and Minot Air Force Base					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT		18. NUMBER OF PAGES
a. REPORT Unclassified	b. ABSTRACT Unclassified	c. THIS PAGE Unclassified	Unclassified		16
19a. NAME OF RESPONSIBLE PERSON Capt Leigh Durden				19b. PHONE NUMBER (Include area code) (937) 938-3297	

Prescribed by ANSI Std. Z39.18



Public Health

DEFENSE HEALTH AGENCY
DEFENSE CENTER FOR PUBLIC HEALTH - DAYTON
2510 5TH STREET, BUILDING 840
WRIGHT-PATTERSON AIR FORCE BASE, OHIO 45433-7951

25 September 2024

MEMORANDUM FOR: AFGSC/SGPB
ATTN: Lt Col Raymond Mak

FROM: DCPH-D/OE
2510 Fifth Street, Building 840
WPAFB OH 45433-7913

SUBJECT: Consultative Letter, AFRL-SA-WP-TR-2024-0012, Missileer Cancer Study,
Malmstrom, F.E. Warren, and Minot Air Force Base (AFB) Round 3 Radon Results

References: (a) Keith J. Westpfahl, Stepanie A. Ohms, Jesse M. Ford, Michael J. Anderson, and
David M. Flint, *Bioenvironmental Engineering Guidebook for Radon Management*
(OH: Air Force Research Laboratory, 2021), p20 & 27.

(b) Agency for Toxic Substances and Disease Registry, *Radon - ToxFAQs* (GA:
ATSDR, 2012).

(c) Crystalyn E. Brown, *U.S. Air Force School of Aerospace Medicine Laboratory
Sampling and Analysis Guide* (OH: Air Force Research Laboratory, 2016), p90.

(d) Environmental Protection Agency, *Health Risk of Radon*. (Washington, D.C.:
EPA, 2023).

(e) Rad Elec, Inc., *Frequently Asked Questions: E-PERMs*. (MD, 2023).

(f) AFMAN 48-148, 20 July 2020, *Ionizing Radiation Protection*.

1. INTRODUCTION

At the request of the Air Force Global Strike Commander (AFGSC/CC), the United States Air Force School of Aerospace Medicine (USAFSAM) Defense Centers for Public Health-Dayton Occupational and Environmental Health Department (DCPH-D/OE) performed an environmental health survey for all forty-five Missile Alert Facilities (MAFs) at Malmstrom AFB, Montana; F.E. Warren AFB, Wyoming; and Minot AFB, North Dakota. The purpose of this environmental health survey was to assess elevated cancer concerns within the Air Force missile community by characterizing and documenting potential exposures to environmental hazards in the MAFs. Round 3 sampling occurred from 11 December 2023 to 15 April 2024 and built upon the Rounds 1 and 2, occurring from 8 June 2023 to 3 October 2023 and 8 September 2023 to 11 January 2024, respectively. Round 3 was executed as part of a three-round

surveillance effort to determine seasonal variations associated with potential environmental hazards at MAF locations. Round 3 repeated area air sampling, direct reading instrument (DRI) air monitoring, drinking water sampling, and soil sampling which were conducted in Rounds 1 & 2. The purpose of this memo is to augment the Round 3 interim reports by conveying Round 3 radon results analyzed by DCPH-D/OE.

A. Installation Personnel:

- (1) Malmstrom AFB: Lt Col Brian Shuler, 341st Operational Medical Readiness Squadron (OMRS) Bioenvironmental Engineering Flight Commander
- (2) F.E. Warren AFB: Capt Ariel Serrano, 90th OMRS Bioenvironmental Engineering Flight Commander
- (3) Minot AFB: Maj Douglas Schneekloth, 5th OMRS Bioenvironmental Engineering Officer in Charge

B. Equipment Used:

- (1) Electret Passive Environmental Radon/Radiation Monitor (E-PERM) Electret Ion Chamber
- (2) E-PERM Electret Reader

2. BACKGROUND

Following a March 2023 site visit to address cancer concerns in the missileer community, DCPH-D/OE performed three rounds of environmental sampling at all MAFs at Malmstrom AFB, F.E. Warren AFB, and Minot AFB. The sampling plan targeted carcinogens which could potentially affect MAF personnel through dermal, ingestion, and inhalation exposure pathways. Radon sampling for all MAFs occurred from 91 to 99 days depending on base and MAF. Round 3 radon sampling at Malmstrom AFB MAFs occurred from 8 January to 15 April 2024. Radon sampling at F.E. Warren from 15 December 2023 to 18 March 2024. Radon sampling at Minot AFB occurred from 11 December 2023 to 21 March 2024. Since all durations exceeded 90 days, they meet Federal and Air Force guidelines for long-term sampling (Westpfahl et al, 2021). Variances in sampling duration occurred between the three bases due to scheduling availability for each base Bioenvironmental Engineering Flight.

When activated, the MAF is manned under two operational tempos. Malmstrom and Minot AFBs man the MAFs for twenty-four hours per day, seven days per week, three hundred sixty-five days a year with rotating crews. Each crew works in the MAF seven straight days at the MAF followed by two weeks in non-MAF locations. F.E. Warren AFB mans the MAFs for twenty-four hours per day, seven days per week, three hundred sixty-five days a year with rotating crews. Each crew works in the MAF for twenty-four hours followed by forty-eight hours in non-MAF locations. Under both tempos, MAFs are occupied for 2,920 hours each year in the Topside Facility Manager Bedroom, Topside Common Area, Topside Security Forces Room, and Launch Control Center (LCC). For the non-continuously occupied location sampled (Hallway to/from LCC), an occupancy of 243 hours each year was applied under the conservative calculation that MAF occupants will occupy the hallway outside of the LCC for five minutes each hour.

3. HEALTH HAZARD SUMMARY

Radon is a naturally occurring, radioactive gas that is odorless, colorless, and tasteless (Agency for Toxic Substances and Disease Registry, 2012). Radon is constantly produced in soil and building materials where uranium exists (Brown, 2016). Because the gas is inert and has a 3.8-day half-life, radon can diffuse through the soil, where it enters the atmosphere or groundwater (Ibid, 2016). Radon in the atmosphere decays into particulate daughter products that adhere to dust particles. Per the EPA, radon is the second leading cause of lung cancer in the United States (EPA, 2023).

4. METHODOLOGY & ANALYSIS

The E-PERM Electret Ion Chamber measures radon concentrations by quantifying the reduction of voltage over a known time (Rad Elec Inc, 2023). Radon concentrations, measured in picocuries per liter (pCi/L), are converted to radon exposures (Working Level Months in a year) through a calculation which incorporates the radon concentration measured by the instrument at the location and the applicable occupancy (hours per year).

Seven E-PERM Electret Ion Chambers in an S Chamber Long-Term (SLT) electret configuration were placed in each MAF. SLT configurations enable thirty to one hundred and twenty days of sampling with a minimum detection limit of 0.2 picocuries per liter (pCi/L). Sample locations within each MAF include one electret placed in the:

- A. Topside Facility Manager Bedroom
- B. Topside Common Area
- C. Topside Security Forces Room
- D. LCC
- E. Hallway to/from LCC

Contrary to Rounds 1 and 2, the *Hallway to/from LCC* locations were not surveyed at Minot AFB. Due to lower occupancy compared to all other locations in the MAFs, previous sampling indicates the *Hallway to/from LCC* location produces the lowest radon exposures, therefore additional sampling was not warranted.

One blank and one duplicate electret were also placed in the LCC. The blank and duplicate are used to ensure quality assurance/quality control (QA/QC). They validate sample results are trustworthy, precise, and unbiased (Westpfahl et al., 2021). Upon completion of the scheduled sampling duration, installation Bioenvironmental Engineering Flight personnel transported the E-PERM Electret Ion Chambers Topside, conducted a radon reading via the E-PERM Electret Reader, and recorded the results on the E-PERM Calculation Spreadsheet. Installation Bioenvironmental Engineering then submitted the E-PERM Calculation Spreadsheet to DCPH-D/OE for final QA/QC. DCPH-D/OE compared the results documented in the E-PERM Calculation Spreadsheet to limits referenced in paragraph 7 of AFMAN 48-148, *Ionizing Radiation Protection*, which direct:

- A. Annual exposure limit to radon is four Working Level Months in a year (4 WLM/yr)
- B. Facility mitigation will begin at exposures greater than 0.8 WLM/yr

5. RESULTS & DISCUSSION

All radon measurements across all forty-five MAFs were below the annual exposure limit and the facility mitigation levels in Chapter 7 of AFMAN 48-148. Therefore, no facility modifications or mitigation to limit radon exposure are recommended. The highest radon levels measured at each installation are:

- A. Malmstrom AFB at MAF Charlie-01 (Topside Facility Manager Bedroom), 0.71 WLM/yr
- B. F.E. Warren AFB at MAF Foxtrot-01 (Topside Security Forces Room), 0.58 WLM/yr
- C. Minot AFB at MAF Charlie-01 (Topside Facility Manager Bedroom), 0.18 WLM/yr

6. CONCLUSIONS

The results presented in this report are a part of a multi-faceted study to characterize the environment where the missileer community works. Three sampling events were executed over a year to determine if seasonal variations exist. Following the publication of all Round 3 reports, DCPH-D/OE will distribute a final report characterizing the health and carcinogenic risks to MAF occupants. If you have any questions, comments, or concerns, please contact Capt Leigh Durden at 937-938-3297 or by e-mail at leigh.durden@us.af.mil.

SCOTT M. BOYD, Lt Col, USAF, BSC
Chief Consulting Executive

3 Attachments

1. Round 3 Radon Results for Malmstrom AFB from 8 January 2024 to 15 April 2024
2. Round 3 Radon Results for F.E. Warren AFB from 15 December 2023 to 18 March 2024
3. Round 3 Radon Results for Minot AFB from 11 December 2023 to 21 March 2024

Attachment 1: Round 3 Radon Results for Malmstrom AFB from 8 January 2024 to 15 April 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
A-01	FM Bedroom	9-Jan-24	13-Apr-24	95	2920	1.3	0.09
A-01	Topside Common Area	9-Jan-24	13-Apr-24	95	2920	0.8	0.05
A-01	Security Forces Room	9-Jan-24	13-Apr-24	95	2920	0.9	0.06
A-01	Hallway to/from LCC	9-Jan-24	13-Apr-24	95	243	2.1	0.01
A-01	LCC	9-Jan-24	13-Apr-24	95	2920	0.7	0.05
B-01	FM Bedroom	9-Jan-24	10-Apr-24	92	2920	0.6	0.04
B-01	Topside Common Area	9-Jan-24	10-Apr-24	92	2920	0.6	0.04
B-01	Security Forces Room	9-Jan-24	10-Apr-24	92	2920	0.1	0.05
B-01	Hallway to/from LCC	9-Jan-24	10-Apr-24	92	243	1.8	0.01
B-01	LCC	9-Jan-24	10-Apr-24	92	2920	2.5	0.17
C-01	FM Bedroom	9-Jan-24	10-Apr-24	92	2920	10.3	0.71
C-01	Topside Common Area	9-Jan-24	10-Apr-24	92	2920	0.5	0.09
C-01	Security Forces Room	9-Jan-24	10-Apr-24	92	2920	0.9	0.06
C-01	Hallway to/from LCC	9-Jan-24	10-Apr-24	92	243	1.6	0.03
C-01	LCC	9-Jan-24	10-Apr-24	92	2920	0.5	0.03
D-01	FM Bedroom	9-Jan-24	9-Apr-24	91	2920	0.6	0.04
D-01	Topside Common Area	9-Jan-24	9-Apr-24	91	2920	0.4	0.03
D-01	Security Forces Room	9-Jan-24	9-Apr-24	91	2920	0.2	0.01
D-01	Hallway to/from LCC	9-Jan-24	9-Apr-24	91	243	1.3	0.01
D-01	LCC	9-Jan-24	9-Apr-24	91	2920	1.2	0.08
E-01	FM Bedroom	9-Jan-24	8-Apr-24	90	2920	1.6	0.11
E-01	Topside Common Area	9-Jan-24	8-Apr-24	90	2920	0.2	0.01
E-01	Security Forces Room	9-Jan-24	8-Apr-24	90	2920	0.9	0.06
E-01	Hallway to/from LCC	9-Jan-24	8-Apr-24	90	243	2.1	0.01
E-01	LCC	9-Jan-24	8-Apr-24	90	2920	0.8	0.05
F-01	FM Bedroom	11-Jan-24	11-Apr-24	91	2920	0.4	0.03
F-01	Topside Common Area	11-Jan-24	11-Apr-24	91	2920	0.4	0.03
F-01	Security Forces Room	11-Jan-24	11-Apr-24	91	2920	0.3	0.02
F-01	Hallway to/from LCC	11-Jan-24	11-Apr-24	91	243	1.1	0.01
F-01	LCC	11-Jan-24	11-Apr-24	91	2920	0.5	0.03

Attachment 1: Round 3 Radon Results for Malmstrom AFB from 8 January 2024 to 15 April 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
G-01	FM Bedroom	11-Jan-24	13-Apr-24	93	2920	0.5	0.03
G-01	Topside Common Area	11-Jan-24	13-Apr-24	93	2920	0.5	0.03
G-01	Security Forces Room	11-Jan-24	13-Apr-24	93	2920	0.4	0.03
G-01	Hallway to/from LCC	11-Jan-24	13-Apr-24	93	243	0.8	0.00
G-01	LCC	11-Jan-24	13-Apr-24	93	2920	0.7	0.05
H-01	FM Bedroom	11-Jan-24	11-Apr-24	91	2920	0.1	0.01
H-01	Topside Common Area	11-Jan-24	11-Apr-24	91	2920	0.0	0.00
H-01	Security Forces Room	11-Jan-24	11-Apr-24	91	2920	0.1	0.01
H-01	Hallway to/from LCC	11-Jan-24	11-Apr-24	91	243	0.6	0.00
H-01	LCC	11-Jan-24	13-Apr-24	91	2920	1.5	0.10
I-01	FM Bedroom	11-Jan-24	14-Apr-24	94	2920	2.2	0.15
I-01	Topside Common Area	11-Jan-24	14-Apr-24	94	2920	0.8	0.05
I-01	Security Forces Room	11-Jan-24	14-Apr-24	94	2920	0.4	0.03
I-01	Hallway to/from LCC	11-Jan-24	14-Apr-24	94	243	2.1	0.01
I-01	LCC	11-Jan-24	14-Apr-24	94	2920	1.7	0.12
J-01	FM Bedroom	11-Jan-24	14-Apr-24	94	2920	2.2	0.15
J-01	Topside Common Area	11-Jan-24	14-Apr-24	94	2920	0.8	0.05
J-01	Security Forces Room	11-Jan-24	14-Apr-24	94	2920	1.0	0.07
J-01	Hallway to/from LCC	11-Jan-24	14-Apr-24	94	243	1.4	0.01
J-01	LCC	11-Jan-24	14-Apr-24	94	2920	0.7	0.05
K-01	FM Bedroom	8-Jan-24	12-Apr-24	95	2920	1.0	0.07
K-01	Topside Common Area	8-Jan-24	12-Apr-24	95	2920	1.1	0.08
K-01	Security Forces Room	8-Jan-24	12-Apr-24	95	2920	0.9	0.06
K-01	Hallway to/from LCC	8-Jan-24	12-Apr-24	95	243	1.6	0.01
K-01	LCC	8-Jan-24	12-Apr-24	95	2920	3.4	0.23
L-01	FM Bedroom	8-Jan-24	15-Apr-24	98	2920	0.1	0.14
L-01	Topside Common Area	8-Jan-24	15-Apr-24	98	2920	2.0	0.03
L-01	Security Forces Room	8-Jan-24	15-Apr-24	98	2920	0.5	0.03
L-01	Hallway to/from LCC	8-Jan-24	15-Apr-24	98	243	0.7	0.00
L-01	LCC	8-Jan-24	15-Apr-24	98	2920	0.5	0.03

Attachment 1: Round 3 Radon Results for Malmstrom AFB from 8 January 2024 to 15 April 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
M-01	FM Bedroom	8-Jan-24	8-Apr-24	91	2920	0.9	0.06
M-01	Topside Common Area	8-Jan-24	8-Apr-24	91	2920	0.8	0.05
M-01	Security Forces Room	8-Jan-24	8-Apr-24	91	2920	0.8	0.05
M-01	Hallway to/from LCC	8-Jan-24	8-Apr-24	91	243	1.4	0.01
M-01	LCC	8-Jan-24	8-Apr-24	91	2920	0.9	0.06
N-01	FM Bedroom	8-Jan-24	12-Apr-24	95	2920	1.0	0.07
N-01	Topside Common Area	8-Jan-24	12-Apr-24	95	2920	0.9	0.06
N-01	Security Forces Room	8-Jan-24	12-Apr-24	95	2920	0.7	0.05
N-01	Hallway to/from LCC	8-Jan-24	12-Apr-24	95	243	1.9	0.01
N-01	LCC	8-Jan-24	12-Apr-24	95	2920	3.0	0.21
O-01	FM Bedroom	8-Jan-24	9-Apr-24	92	2920	1.2	0.08
O-01	Topside Common Area	8-Jan-24	9-Apr-24	92	2920	1.0	0.07
O-01	Security Forces Room	8-Jan-24	9-Apr-24	92	2920	1.2	0.08
O-01	Hallway to/from LCC	8-Jan-24	9-Apr-24	92	243	2.7	0.02
O-01	LCC	8-Jan-24	9-Apr-24	92	2920	0.7	0.05

**Attachment 2: Round 3 Radon Results for F.E. Warren AFB from 15 December 2023 to
18 March 2024**

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
A-01	FM Bedroom	15-Dec-23	18-Mar-24	94	2920	1.2	0.08
A-01	Topside Common Area	15-Dec-23	18-Mar-24	94	2920	1.0	0.07
A-01	Security Forces Room	15-Dec-23	18-Mar-24	94	2920	0.6	0.04
A-01	Hallway to/from LCC	15-Dec-23	18-Mar-24	94	243	1.0	0.01
A-01	LCC	15-Dec-23	18-Mar-24	94	2920	0.4	0.03
B-01	FM Bedroom	11-Dec-23	11-Mar-24	94	2920	0.3	0.02
B-01	Topside Common Area	11-Dec-23	11-Mar-24	94	2920	0.5	0.03
B-01	Security Forces Room	11-Dec-23	11-Mar-24	94	2920	0.3	0.02
B-01	Hallway to/from LCC	11-Dec-23	11-Mar-24	94	243	0.6	0.00
B-01	LCC	11-Dec-23	11-Mar-24	94	2920	0.0	0.00
C-01	FM Bedroom	11-Dec-23	11-Mar-24	91	2920	0.8	0.05
C-01	Topside Common Area	11-Dec-23	11-Mar-24	91	2920	0.8	0.05
C-01	Security Forces Room	11-Dec-23	11-Mar-24	91	2920	1.1	0.08
C-01	Hallway to/from LCC	11-Dec-23	11-Mar-24	91	243	1.6	0.01
C-01	LCC	11-Dec-23	11-Mar-24	91	2920	0.8	0.05
D-01	FM Bedroom	11-Dec-23	11-Mar-24	91	2920	1.3	0.09
D-01	Topside Common Area	11-Dec-23	11-Mar-24	91	2920	1.3	0.09
D-01	Security Forces Room	11-Dec-23	11-Mar-24	91	2920	1.6	0.11
D-01	Hallway to/from LCC	11-Dec-23	11-Mar-24	91	243	1.5	0.01
D-01	LCC	11-Dec-23	11-Mar-24	91	2920	1.1	0.08
E-01	FM Bedroom	15-Dec-23	18-Mar-24	94	2920	1.1	0.08
E-01	Topside Common Area	15-Dec-23	18-Mar-24	94	2920	0.0	0.00
E-01	Security Forces Room	15-Dec-23	18-Mar-24	94	2920	0.9	0.06
E-01	Hallway to/from LCC	15-Dec-23	18-Mar-24	94	243	1.5	0.01
E-01	LCC	15-Dec-23	18-Mar-24	94	2920	0.7	0.08
F-01	FM Bedroom	13-Dec-23	13-Mar-24	91	2920	1.4	0.10
F-01	Topside Common Area	13-Dec-23	13-Mar-24	91	2920	1.3	0.09
F-01	Security Forces Room	13-Dec-23	13-Mar-24	91	2920	8.4	0.58
F-01	Hallway to/from LCC	13-Dec-23	13-Mar-24	91	243	1.6	0.01
F-01	LCC	13-Dec-23	13-Mar-24	91	2920	0.9	0.06

Attachment 2: Round 3 Radon Results for F.E. Warren AFB from 15 December 2023 to

18 March 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
G-01	FM Bedroom	14-Dec-23	14-Mar-24	91	2920	1.3	0.09
G-01	Topside Common Area	14-Dec-23	14-Mar-24	91	2920	0.9	0.06
G-01	Security Forces Room	14-Dec-23	14-Mar-24	91	2920	1.5	0.10
G-01	Hallway to/from LCC	14-Dec-23	14-Mar-24	91	243	0.8	0.00
G-01	LCC	14-Dec-23	14-Mar-24	91	2920	0.9	0.06
H-01	FM Bedroom	14-Dec-23	14-Mar-24	91	2920	1.2	0.08
H-01	Topside Common Area	14-Dec-23	14-Mar-24	91	2920	1.0	0.07
H-01	Security Forces Room	14-Dec-23	14-Mar-24	91	2920	1.1	0.08
H-01	Hallway to/from LCC	14-Dec-23	14-Mar-24	91	243	1.9	0.01
H-01	LCC	14-Dec-23	14-Mar-24	91	2920	0.4	0.03
I-01	FM Bedroom	15-Dec-23	18-Mar-24	94	2920	1.1	0.08
I-01	Topside Common Area	15-Dec-23	18-Mar-24	94	2920	1.2	0.08
I-01	Security Forces Room	15-Dec-23	18-Mar-24	94	2920	1.1	0.08
I-01	Hallway to/from LCC	15-Dec-23	18-Mar-24	94	243	1.1	0.01
I-01	LCC	15-Dec-23	18-Mar-24	94	2920	0.8	0.05
J-01	FM Bedroom	13-Dec-23	13-Mar-24	91	2920	1.3	0.09
J-01	Topside Common Area	13-Dec-23	13-Mar-24	91	2920	1.8	0.12
J-01	Security Forces Room	13-Dec-23	13-Mar-24	91	2920	1.8	0.12
J-01	Hallway to/from LCC	13-Dec-23	13-Mar-24	91	243	1.0	0.01
J-01	LCC	13-Dec-23	13-Mar-24	91	2920	0.9	0.06
K-01	FM Bedroom	14-Dec-23	14-Mar-24	91	2920	12	0.08
K-01	Topside Common Area	14-Dec-23	14-Mar-24	91	2920	0.5	0.03
K-01	Security Forces Room	14-Dec-23	14-Mar-24	91	2920	1.1	0.08
K-01	Hallway to/from LCC	14-Dec-23	14-Mar-24	91	243	0.4	0.00
K-01	LCC	14-Dec-23	14-Mar-24	91	2920	1.2	0.08
L-01	FM Bedroom	13-Dec-23	13-Mar-24	91	2920	1.5	0.10
L-01	Topside Common Area	13-Dec-23	13-Mar-24	91	2920	1.0	0.07
L-01	Security Forces Room	13-Dec-23	13-Mar-24	91	2920	1.2	0.08
L-01	Hallway to/from LCC	13-Dec-23	13-Mar-24	91	243	1.2	0.01
L-01	LCC	13-Dec-23	13-Mar-24	91	2920	0.6	0.04

Attachment 2: Round 3 Radon Results for F.E. Warren AFB from 15 December 2023 to

18 March 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
M-01	FM Bedroom	12-Dec-23	12-Mar-24	91	2920	1.7	0.12
M-01	Topside Common Area	12-Dec-23	12-Mar-24	91	2920	1.2	0.08
M-01	Security Forces Room	12-Dec-23	12-Mar-24	91	2920	1.5	0.10
M-01	Hallway to/from LCC	12-Dec-23	12-Mar-24	91	243	1.5	0.01
M-01	LCC	12-Dec-23	12-Mar-24	91	2920	0.9	0.06
N-01	FM Bedroom	12-Dec-23	12-Mar-24	91	2920	1.7	0.12
N-01	Topside Common Area	12-Dec-23	12-Mar-24	91	2920	1.4	0.10
N-01	Security Forces Room	12-Dec-23	12-Mar-24	91	2920	1.2	0.08
N-01	Hallway to/from LCC	12-Dec-23	12-Mar-24	91	243	2.0	0.01
N-01	LCC	12-Dec-23	12-Mar-24	91	2920	1.5	0.10
O-01	FM Bedroom	12-Dec-23	12-Mar-24	91	2920	0.9	0.06
O-01	Topside Common Area	12-Dec-23	12-Mar-24	91	2920	0.5	0.03
O-01	Security Forces Room	12-Dec-23	12-Mar-24	91	2920	1.1	0.08
O-01	Hallway to/from LCC	12-Dec-23	12-Mar-24	91	243	1.2	0.01
O-01	LCC	12-Dec-23	12-Mar-24	91	2920	1.3	0.09

Attachment 3: Round 3 Radon Results for Minot AFB from 11 December 2023 to 21 March 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
A-01	FM Bedroom	11-Dec-23	18-Mar-24	98	2920	1.6	0.06
A-01	Topside Common Area	11-Dec-23	18-Mar-24	98	2920	0.9	0.07
A-01	Security Forces Room	11-Dec-23	18-Mar-24	98	2920	1.0	0.02
A-01	Hallway to/from LCC	Location Not Sampled					
A-01	LCC	11-Dec-23	18-Mar-24	98	2920	0.4	0.03
B-01	FM Bedroom	11-Dec-23	18-Mar-24	98	2920	1.8	0.13
B-01	Topside Common Area	11-Dec-23	18-Mar-24	98	2920	0.5	0.03
B-01	Security Forces Room	11-Dec-23	18-Mar-24	98	2920	0.9	0.06
B-01	Hallway to/from LCC	Location Not Sampled					
B-01	LCC	11-Dec-23	18-Mar-24	98	2920	2.2	0.15
C-01	FM Bedroom	11-Dec-23	18-Mar-24	98	2920	3.3	0.18
C-01	Topside Common Area	11-Dec-23	18-Mar-24	98	2920	1.3	0.09
C-01	Security Forces Room	11-Dec-23	18-Mar-24	98	2920	1.3	0.09
C-01	Hallway to/from LCC	Location Not Sampled					
C-01	LCC	11-Dec-23	18-Mar-24	98	2920	1.9	0.13
D-01	FM Bedroom	13-Dec-23	19-Mar-24	97	2920	2.0	0.14
D-01	Topside Common Area	13-Dec-23	19-Mar-24	97	2920	2.5	0.17
D-01	Security Forces Room	13-Dec-23	19-Mar-24	97	2920	1.3	0.09
D-01	Hallway to/from LCC	Location Not Sampled					
D-01	LCC	13-Dec-23	19-Mar-24	97	2920	1.9	0.13
E-01	FM Bedroom	13-Dec-23	19-Mar-24	97	2920	1.0	0.07
E-01	Topside Common Area	13-Dec-23	19-Mar-24	97	2920	1.0	0.07
E-01	Security Forces Room	13-Dec-23	19-Mar-24	97	2920	1.0	0.07
E-01	Hallway to/from LCC	Location Not Sampled					
E-01	LCC	13-Dec-23	19-Mar-24	97	2920	0.9	0.06
F-01	FM Bedroom	13-Dec-23	19-Mar-24	97	2920	1.6	0.11
F-01	Topside Common Area	13-Dec-23	19-Mar-24	97	2920	0.7	0.05
F-01	Security Forces Room	13-Dec-23	19-Mar-24	97	2920	0.6	0.04
F-01	Hallway to/from LCC	Location Not Sampled					
F-01	LCC	13-Dec-23	19-Mar-24	97	2920	0.8	0.05

Attachment 3: Round 3 Radon Results for Minot AFB from 11 December 2023 to 21 March 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
G-01	FM Bedroom	13-Dec-23	19-Mar-24	97	2920	1.4	0.10
G-01	Topside Common Area	13-Dec-23	19-Mar-24	97	2920	1.4	0.10
G-01	Security Forces Room	13-Dec-23	19-Mar-24	97	2920	1.5	0.10
G-01	Hallway to/from LCC	Location Not Sampled					
G-01	LCC	13-Dec-23	19-Mar-24	97	2920	0.2	0.01
H-01	FM Bedroom	12-Dec-23	20-Mar-24	99	2920	1.2	0.08
H-01	Topside Common Area	12-Dec-23	20-Mar-24	99	2920	0.9	0.06
H-01	Security Forces Room	12-Dec-23	20-Mar-24	99	2920	1.0	0.07
H-01	Hallway to/from LCC	Location Not Sampled					
H-01	LCC	12-Dec-23	20-Mar-24	99	2920	0.2	0.01
I-01	FM Bedroom	12-Dec-23	20-Mar-24	99	2920	0.8	0.05
I-01	Topside Common Area	12-Dec-23	20-Mar-24	99	2920	0.6	0.04
I-01	Security Forces Room	12-Dec-23	20-Mar-24	99	2920	1.8	0.12
I-01	Hallway to/from LCC	Location Not Sampled					
I-01	LCC	12-Dec-23	20-Mar-24	99	2920	1.2	0.06
J-01	FM Bedroom	12-Dec-23	20-Mar-24	99	2920	0.4	0.03
J-01	Topside Common Area	12-Dec-23	20-Mar-24	99	2920	0.0	0.00
J-01	Security Forces Room	12-Dec-23	20-Mar-24	99	2920	1.2	0.08
J-01	Hallway to/from LCC	Location Not Sampled					
J-01	LCC	12-Dec-23	20-Mar-24	99	2920	0.8	0.05
K-01	FM Bedroom	12-Dec-23	20-Mar-24	99	2920	0.2	0.01
K-01	Topside Common Area	12-Dec-23	20-Mar-24	99	2920	0.0	0.00
K-01	Security Forces Room	12-Dec-23	20-Mar-24	99	2920	1.0	0.07
K-01	Hallway to/from LCC	Location Not Sampled					
K-01	LCC	12-Dec-23	20-Mar-24	99	2920	0.3	0.02
L-01	FM Bedroom	14-Dec-23	21-Mar-24	98	2920	2.1	0.14
L-01	Topside Common Area	14-Dec-23	21-Mar-24	98	2920	0.0	0.00
L-01	Security Forces Room	14-Dec-23	21-Mar-24	98	2920	1.0	0.07
L-01	Hallway to/from LCC	Location Not Sampled					
L-01	LCC	14-Dec-23	21-Mar-24	98	2920	0.1	0.01

Attachment 3: Round 3 Radon Results for Minot AFB from 11 December 2023 to 21 March 2024

MAF	Location	Start Date	End Date	Total Days Exposed	Bldg Occupancy (hrs/yr)	Radon in Air (pCi/L)	Radon in Air (WLM/yr)
M-01	FM Bedroom	14-Dec-23	21-Mar-24	98	2920	1.0	0.07
M-01	Topside Common Area	14-Dec-23	21-Mar-24	98	2920	1.7	0.12
M-01	Security Forces Room	14-Dec-23	21-Mar-24	98	2920	1.4	0.10
M-01	Hallway to/from LCC	Location Not Sampled					
M-01	LCC	14-Dec-23	21-Mar-24	98	2920	1.0	0.07
N-01	FM Bedroom	14-Dec-23	21-Mar-24	98	2920	1.3	0.09
N-01	Topside Common Area	14-Dec-23	21-Mar-24	98	2920	1.5	0.10
N-01	Security Forces Room	14-Dec-23	21-Mar-24	98	2920	0.6	0.04
N-01	Hallway to/from LCC	Location Not Sampled					
N-01	LCC	14-Dec-23	21-Mar-24	98	2920	0.5	0.03
O-01	FM Bedroom	14-Dec-23	21-Mar-24	98	2920	1.6	0.11
O-01	Topside Common Area	14-Dec-23	21-Mar-24	98	2920	1.7	0.12
O-01	Security Forces Room	14-Dec-23	21-Mar-24	98	2920	2.2	0.15
O-01	Hallway to/from LCC	Location Not Sampled					
O-01	LCC	14-Dec-23	21-Mar-24	98	2920	0.8	0.05